

Outboards

VERADO | FOURSTROKE | PRO XS | RACING





MERCURY RACING

MARINE TECHNOLOGY

MARINE TECHNOLOGY

WIDE-OPEN

MERCURY

Racing 450

Pro



Bold is who we are

Soon after Carl Kiekhaefer left his Wisconsin family farm in 1939, founded Mercury Marine® and changed the course of the boating industry forever, Mercury® was recognized as a powerful leader in the marine industry – a position strengthened by each ensuing Mercury innovation. Today, Mercury's heritage is rich with success born from a culture of knowledge, commitment and uncompromising standards, and bold has always been the unifying factor in the decisions and actions that led us to become the leader in marine propulsion. Bold not only drives us to produce extremely reliable engines with exceptional performance, it leads us to invent our own alloys, to design the most innovative controls and rigging, to create experience-enhancing propellers, and to offer the finest marine parts and accessories.

But above all else, bold is our commitment to deliver confidence, enjoyment and the greatest experiences on the water.

Welcome to Mercury, where bold is who we are.

VERADO®

Our premium outboard platform redefines the category with advanced engineering, innovative technology and refined operation.

250 - 400 HP

9

FOURSTROKE

Backed by decades of experience on water all over the world, our FourStroke models deliver reliable, economical performance you can count on season after season.

2.5 - 225 HP

19

GO BOLDLY.™

PRO XS®

Outboards with the hard-charging performance to put you out front and keep you there, Pro XS is the choice of tournament anglers and performance enthusiasts.



115 - 300 HP

43

MERCURY RACING

For us, innovation isn't optional. Our line of outboards springs from a heritage of uncompromising breakthroughs.



250 - 450 HP

49

VERADO	7
250 / 300 Verado	8
350 / 400 Verado	12
FOURSTROKE	17
175 / 200 / 225 FourStroke	18
150 FourStroke	22
80 / 100 / 115 FourStroke	24
40 / 50 / 60 FourStroke	26
25 / 40 / 65 / 80 Jet Outboard	28
25 / 30 FourStroke	30
15 / 20 FourStroke	32
15 ProKicker	34
8 / 9.9 FourStroke	36
2.5 / 3.5 / 4 / 5 / 6 FourStroke	38
5 Propane FourStroke	40

PRO XS	43
175 / 200 / 225 / 250 / 300 Pro XS	44
115 / 150 Pro XS	46
MERCURY RACING	49
250R / 300R	50
Verado 400R	52
450R	54
PARTS AND ACCESSORIES	59
OUTBOARD GEARCASES	62
MERCURY PROPELLERS	65
MERCURY CONTROLS & RIGGING	70
SPECIFICATIONS	78
WELCOME TO THE MERCURY COLLECTION SHOP	83



UNRIVALED DRIVING EXPERIENCE



Verado

Ultimate performance meets ultimate refinement

True greatness believes it can always be greater. It doesn't settle. There is no finish line. It is an ever-evolving work in progress. But it can always show you how far it has come. This is Verado – amazingly quiet and smooth, exhilaratingly quick out of the hole, fast, fuel-efficient and powerful. It's the most refined outboard in history, and it's created for those who settle for nothing but the best.

Mercury Verado doesn't just sound quiet, it also feels quiet. The inline cylinder design is perfectly balanced. The **Advanced MidSection** used on the V-8 and inline 6 cylinder models utilises an unique mount system, which isolates the powerhead to virtually eliminate vibration.



250 / 300 Verado

Exhilarating Performance

The smooth, refined power of a V-8 4.6-litre powerhead delivers exhilarating acceleration and top speed to run offshore with confidence, with generous displacement and robust design that provide uncompromising durability and reliability. The Mercury-exclusive **Advanced MidSection (AMS)** and under-cowl noise management features set the standard for smooth, quiet marine propulsion.

No outboard in the class offers more displacement than the Verado V-8 4.6-litre. The performance-inspired 32-valve double-overhead-cam (DOHC) design and long, tuned intake runners produce more torque and allow the engine to reach higher engine speeds (rpm) faster. Weight is trimmed to 272 kilos for improved power-to-weight. Transient Spark calibration optimizes spark timing to boost hole-shot torque by as much as 7 percent, so you can get on plane and get going in an instant.

PREMIUM V-8 POWER

HP	Disp (cc)	Engine type	Dry Weight*
300	4600	V-8	272 kg
250	4600	V-8	272 kg

*Lightest model available



Superior fuel economy

V-8 Verado outboards deliver superior fuel economy at cruising speed and wide-open throttle. Advanced Range Optimization (ARO) calibration precisely adjusts the fuel mixture and delivers the best possible efficiency at any speed. Verado V-8 outboards are calibrated to deliver full performance on 87-octane fuel.

Smooth and quiet

250 hp and 300 hp Verado deliver class-leading smooth and quiet performance. The next-generation **Advanced MidSection (AMS)** moves engine mounts aft and outward to virtually eliminate vibration. Engine noise is minimized by a tuned multi-chamber air intake, fuel-injector covers that decrease high-frequency noise, and a highly engineered cowl sealing system.

Corrosion resistance

Not only are Verado outboards designed and built to withstand the rigors of saltwater operation, they're backed by a three-year anti-corrosion warranty – a significant advantage over competitors' products.



Verado V-8 advantages

Adaptive Speed Control

Whether you're heading up a swell or into a tight turn, Adaptive Speed Control on V-8 Verado outboards automatically maintains the set rpm even as load or conditions change. That means you make far fewer throttle adjustments.

Advanced Sound Control

You can customize the exhaust tone of a V-8 Verado outboard with industry-exclusive Advanced Sound Control. The dual muffler system allows you to toggle between an ultra-quiet mode and a deeper, sportier tone.

Extra charging power

V-8 Verado outboards keep batteries charged and ready on boats rigged with power-draining accessories. The Idle Charge battery-management system automatically increases idle rpm to boost alternator output and recharge low batteries to the proper level.

Graphite Grey



Redline Red



Mercury Silver



Pacific Blue



White, Black, Your Choice

Mercury's Cold Fusion White and traditional Phantom Black are available on the 250 hp and 300 hp Verado outboards.



Cold Fusion White

Phantom Black

Expanded colour options

For ultimate personalization of 250 and 300hp Verado outboards, four colours of factory-painted accent panels are available as kits. The panels are made from thin and durable polycarbonate that adhere firmly and provide colour harmonization with a wide variety of boat colours.



Effortless Operation

Verado comes standard with SmartCraft® Digital Throttle & Shift (DTS) for ultra-smooth shifting, instantaneous throttle response, as well as electro-hydraulic, automotive-style power steering that provides precision handling.



Pop the top

V-8 Verado features a top cowl service door that enables easy engine-oil checks and fills. A single push opens the watertight door for access to the dipstick, service decal, and carrying handle.

Keep it fresh

A convenient, easily accessed cowl-mounted freshwater flush system allows periodic removal of salt from internal water passages.



INDUSTRY-LEADING

CORROSION RESISTANCE

Not only are Verado outboards designed and built to withstand the rigors of saltwater operation, they're backed by a three-year anti-corrosion warranty – a significant advantage over competitors' products.



350 / 400 Verado

Legendary power

Supercharged torque from the lightweight 2.6L L6 powerhead hits the instant you drop the digital throttle! Tuned to power the heaviest offshore boats out of the hole and over the swell.

Quality and reliability comes as standard. That's why the 350 and the 400 hp Verado were designed with features like a long bolt design, which passes through the entire engine block and cylinder head keeping the powerhead in a constant state of compression and improving reliability by eliminating the effects of expansion and contraction. Also the exclusive Mercury Integrated Oil Cooler improves Verado's long term durability by maintaining proper oil temperature and reducing oil dilution.

SMOOTHEST, QUIETEST

HP	Disp (cc)	Engine type	Dry Weight*
400	2600	Inline 6	303 kg
350	2600	Inline 6	303 kg

*Lightest model available



Built to take it

350 and the 450 hp Verado are made for bigger boats and big water, with superior Mercury corrosion protection provided by exclusive alloys, finishes and relentless durability testing. They also feature a robust long-bolt powerhead design, maintenance-free valve train, and dual water inlets for consistent cooling and longer life.

Digital Throttle & Shift for incredible response

SmartCraft® Digital Throttle & Shift delivers instant, smooth response. No lag, no waiting. Just the precise control and smooth operation you want from your outboard experience. An experience made even better with the true power steering of Verado (standard on six-cylinder models) for effortless control and minimal steering torque.

Power. Like you've never felt it before

Not at the steering wheel. Not at the throttle. More like the seat of your pants. Thanks to the perfectly-balanced in-line six-cylinder design and our **Advanced Mid Section (AMS)** design with perimeter mounts. You're as close to quiet, vibration-free running as anything on the water. Or land for that matter.

Corrosion protection that's way more than skin deep

It's an all-out fight. And we go all out to help you win by starting with corrosion-resistant low-copper aluminium alloys, then adding an internal Salt Shield coating and a MercFusion™ layered painting process.

One protective barrier after another, dedicated to shielding critical engine and drive components from nature's harshest, most corrosive elements, and backed by the industry's only 3-year corrosion warranty. Because your peace of mind is worth protecting too.



2.6 L L6 Verado advantages

Smoothest, quietest

The inherently balanced in-line six-cylinder engine and our Advanced Mid Section (AMS) with perimeter mounts virtually eliminate vibration in the boat.

Freshwater flush

Mercury's patented easy accessible flush system lets you flush the engine from inside or outside of the boat. It's engineered to keep the hose from kinking, and the flush-mounted cap is secured to the engine for convenience.



Integrated steering

Mercury Verado offers integrated Electro Hydraulic Power-steering, whether your use is single or multiple engines, inshore or offshore applications steering loads will always be low. With more than 80 years experience in building marine systems we know what works best.

White, Black, Your Choice

In addition to traditional Mercury Phantom Black, our popular Cold Fusion cowls are now available down to 200hp.



Phantom Black



Cold Fusion White



Maintenance-free valve train

Thanks to “Lash for Life” valve train technology, you’ll never have to bring your outboard to a dealer for an expensive valve-lash adjustment. Unlike other four-strokes, these truly are maintenance-free.

Optimized guide plates

More horsepower means operating at higher speeds, which, while exciting, requires greater vessel control. Exclusive, optimized guide plates give the Mercury Verado 350 superior handling at high speeds, which means greater confidence in hard-running situations.

Styled vented flywheel cover

The Mercury Verado 350 and 450 hp outboards have vents in its flywheel cover that allow engine heat to dissipate more easily. Lower operating temperatures help to improve the efficiency and durability of the engine, and its components.





POWER YOUR ADVENTURE. POWER YOUR FUN.



FourStroke

Built to be reliable, powerful and efficient

If you demand absolute confidence in your outboard, look no further than Mercury FourStrokes. In addition to world-class reliability, they're light and compact with awesome performance and pleasing fuel-efficiency. Mercury FourStrokes feature:

- Technically advanced, consumer-focused designs.
- Easy-to-use controls and intuitive maintenance for an improved ownership experience.
- Precise fuel-delivery systems that produce awesome performance and fuel efficiency.
- A broad product portfolio that provides more consumer options and flexibility.

Mercury FourStroke is high-tech without high stress. It's the answer to worry-free boating from a powerful and reliable engine.

Bold doesn't always mean large. Mercury's lower-horsepower FourStroke outboards are engineered to deliver amazing performance in a package that's as light and efficient as possible. With innovative designs and advanced technology, these compact and versatile Mercury outboards are quiet, responsive and reliable in the shallows and on open water.



175 / 200 / 225 FourStroke

Greater performance for awesome boating

The Mercury FourStrokes are precision engineered from skeg to cowl. Packed with advanced technology to improve all aspects of performance and reliability, the robust 3.4-litre V-6 engines – designed to minimize weight and maximize fuel economy – deliver Mercury's best-ever FourStroke hole shot, top speed and fuel efficiency. The FourStrokes also provide unsurpassed dampening of sound and vibration for a superior boating experience, and Idle Charge battery-management prevents boaters from draining their batteries while operating multiple electronic devices.

The compact profile is ideal for a broad range of multi-engine applications. For easy engine oil checks, just pop open the Top Cowl Service Door. And the V-6 FourStroke, available with mechanical or Digital Throttle and Shift controls for enhanced versatility and repower compatibility, looks like nothing else on the water. Bold, contemporary styling is inspired by speed and power, and multiple colour options make it easy to personalize.

FASTER, QUICKER, MORE EFFICIENT

HP	Disp (cc)	Engine type	Dry Weight*
225	3400	V-6	216 kg
200	3400	V-6	216 kg
175	3400	V-6	216 kg

*Lightest model available



Get on plane faster

- Our quickest and fastest 200 hp FourStroke with class-leading V-6 200 hp displacement.
- Performance-inspired quick-revving double-overhead camshaft design and deep-breathing intake.
- The lightest weight in the category.

All these contribute to unmatched hole-shot performance on a wide range of boat types. Make the most of that acceleration with the broad range of pitch-perfect Mercury propellers, expanded to match the performance of these outboards.

Best-ever FourStroke fuel economy

Go farther with every litre! **Advanced Range Optimization (ARO)** and closed-loop fuel control work together to precisely adjust the fuel mixture and deliver the best possible efficiency. Details such as bearing sizes and oil-flow scheme have been engineered to reduce internal friction and improve overall efficiency. A hydrodynamically efficient gearcase slips through the water so the outboard has less work to do.

Compact and light

Gram by gram, Mercury engineers cut weight from the Mercury FourStroke outboards, resulting in the lightest engines in their class. Less weight improves every aspect of performance. The V-6 powerhead configuration has been optimized to minimize size, and the single-latch cowl is designed to hug the powerhead. The V-6 FourStrokes mount tightly together, which helps them fit a broader range of transoms – ideal for simple, seamless repower applications.



FourStroke advantages

Versatility

The V-6 FourStroke outboards are available with mechanical or digital controls, providing consumers more options in new-boat and repower applications. Consumers can choose between hydraulic (standard) or power steering (optional).


Adaptive Speed Control (ASC)

ASC allows consumers to maintain engine speed (rpm) regardless of load or condition changes – such as rough water, tight turns, tow sports and lower speeds on plane – without having to frequently adjust throttle position.



Low-voltage battery-management

Idle Charge battery-management prevents boaters from draining their batteries while operating multiple electronic devices. When battery voltage is reduced, the engine will automatically increase idle rpm to boost alternator output and recharge low batteries to the proper level.



Cold Fusion White

Phantom Black

White, Black, Your Choice

Mercury's Cold Fusion White and traditional Phantom Black are available on the 200hp and 225hp FourStroke outboards.

Expanded colour options

Mercury's Cold Fusion White and traditional Phantom Black are available on the 200hp and 225hp FourStroke outboards.

For ultimate personalization, four colours of factory-painted accent panels are available as kits. The panels are made of thin and durable polycarbonate that adhere firmly and provide colour harmonization.



Graphite Grey

Mercury Silver

Pacific Blue

Redline Red



Maintenance made easy

Clear information for routine maintenance is provided on an engine decal under the cowl. The decal provides a quick, easy overview of routine maintenance intervals checks, along with required quantities and types of engine and gearcase oil, spark plugs, etc.

Top cowl service door

For easy and simple engine oil checks, just pop open the new Service Door on top of the cowl. A single push opens the watertight door for access to the dipstick and service decal inside. Service door also provides access to a carrying handle, and blends back into the cowl when closed.





150 FourStroke

Exceeding the boundaries of reliability

The mission to our engineers was: design and make the most reliable 150hp FourStroke outboard in the industry. To do that they started with a strong 3.0L block capable of producing more than 250hp and asked it to deliver only 150hp. Doing so greatly increases the powerhead's long term durability.

Add to this class leading displacement engine a robust gearcase and nearly 10,000 hours of engineering and field testing, then back it all up with an industry leading limited 5-year factory backed warranty, you can see why we consider their mission accomplished.

Additionally it's small, compact design makes it a perfect fit with a wide range of boating applications. All this, and it still weighs in at a light, fuel-saving 206 kg.

COMPACT AND VERSATILE

HP	Disp (cc)	Engine type	Dry Weight*
150	3000	Inline 4	206 kg

*Lightest model available



Perfect for repower

The compact, lightweight design of Mercury's 150 hp FourStroke can be mounted on tight boat transoms, for boats on a trailer every kilo saved is a benefit during transportation. The 150 FourStroke is also flexible enough to accommodate mechanical or hydraulic steering, mechanical control/cable systems and a full complement of instruments.

Don't stress out

Work less, do more. Sounds good, right? That's the key behind the 150 hp Mercury FourStroke. With 3.0L displacement this 4 cylinder single overhead cam design works less to produce more torque and horsepower, which means exceptional durability and long-term peace of mind.

Lightweight powerhouse

Typically the higher the displacement, the higher the weight. Not in the case of the 150 hp Mercury FourStroke. The 150 is the lightest engine in its class, this 150 hp FourStroke is a great fit for repower and new boat packages alike.

Less time in the shop

The 150 hp FourStroke looks good with the cowl on or off, with convenient and easy access to perform basic maintenance. Add in the no-spill oil change system, an easy access fuel filter and a maintenance-free valve train and you've got one of the easiest to maintain outboards on the market today.





80 / 100 / 115 FourStroke

High displacement / Less weight

Thanks to Mercury's never-ending commitment to provide industry-leading innovation, now you can hang a lighter, more compact FourStroke outboard on your transom that delivers better performance, hole shot and tow sport capability than the previous 80-115hp models – along with increased fuel savings, hassle-free maintenance and rugged reliability.

These FourStroke outboards displace 2.1 litres, which means they work smarter – not harder – leading to improved durability and longer life, not to mention greater hole shot, superior overall acceleration and awesome top speed.

Less weight combined with high displacement helps these FourStroke outboards provide maximum fuel efficiency, especially at cruising speeds. Specialized oil scrapers and bearings minimize friction in the crankshaft, also resulting in decreased fuel consumption.

Sound and vibration are minimized by the tightly sealed, thermo-bonded cowl; the Idle-Relief Muffler, which utilises an acoustic filter to reduce high-frequency exhaust noise; a smooth clutch design; and Mercury's exclusive Focused Mount System.

PERFECT POWER-TO-WEIGHT RATIO

HP	Disp (cc)	Engine type	Dry Weight*
115	2064	Inline 4	163 kg
115 CT	2064	Inline 4	165 kg
100	2064	Inline 4	163 kg
100 CT	2064	Inline 4	165 kg
80	2064	Inline 4	163 kg

*Lightest model available



Large and in charge

Need more muscle? Upgrade to a Command Thrust model with its larger gearcase and 2.38:1 gear ratio. Paired with Mercury's V-6-class big-diameter propellers, the 100 & 115hp FourStroke delivers even better acceleration, awesome manoeuvrability and superior stopping power.

Heavy Duty

This larger gearcase footprint, combined with the robust 2.38:1 gear ratio and access to Mercury's class-leading offering of large outboard propellers, is the perfect combination for pontoons, larger/heavier fibreglass or aluminium fishing and pleasure boats or heavy-duty commercial applications.

Counter-rotation

For the first time, Mercury is offering a 115 hp FourStroke with left-hand rotation. The addition of a counter-rotation model provides neutral steering feel and superior handling in a twin-engine rig. Two 115 Command Thrust engines on the transom provide the manoeuvrability and get-home safety of higher-horsepower twins – at a much lower price.

Improved acceleration

The larger "CT" gearcase provides more leverage to lift heavier hulls onto plane and keep them on plane at lower speeds. The 2.38:1 gear ratio lets the engine spin up more rapidly, developing torque at a faster rate.

Reasons to repower

A new Mercury FourStroke can re-energize your boat with improved acceleration, performance and manoeuvrability. The industry's lightest 115hp FourStroke weighs just 163kg, these FourStrokes are 18kg lighter than the prior generation of Mercury FourStrokes and 9kg lighter than the nearest competitor.

They're a great fit even on transoms that can't handle the weight of older, heavier FourStrokes, and their sleek, low profiles make them easier to fish over and around.

PRIOR 80-115HP

NEW 80-115HP





40 / 50 / 60 FourStroke

High displacement / Less weight

The Mercury 40 hp to 60 hp EFI engines provide enhanced SmartCraft capability a comprehensive boat and propulsion monitoring system, supplying detailed engine status and performance data for virtually all engine functions such as trim, speed, rpm, troll control, fuel flow and for a wealth of boat functions, like fuel level, battery voltage.

SmartCraft also provides Engine Guardian by protecting your engine by constantly monitoring engine sensors and providing early indication of the unlikely event that the engine is not operating as designed, and proactively taking corrective action when needed.

Mercury's 40 hp to 60 hp full SmartCraft capability also provide a possibility to upgrade with an optional Theft Deterrence System (TDS) or Mercury's advanced Active Trim system.

SMARTCRAFT DIGITAL KNOWLEDGE

HP	Disp (cc)	Engine type	Dry Weight*
60 EFI CT	995	Inline 4	118 kg
60 EFI	995	Inline 4	112 kg
50 EFI	995	Inline 4	112 kg

*Lightest model available





More Control

The Mercury 60 Command Thrust model(s) have a taller gearcase, oversized prop and lower gear ratio, they deliver more thrust and control than any other outboard of comparable horsepower.

Increased thrust is delivered by a 2.33:1 gear ratio with 44% larger gears.



The Big Tiller

Mercury's optional Big Tiller popularity has increased for use on open inflatables, ribs and fibreglass boats where the longer tiller grip with convenient mounted power trim switch for easy access is easy and safe to operate at your fingertips. Sport fishers like the optional slow speed (troll) control feature that allows for setting the slow boat-speed precisely at the speed the fish will bite.



HP	Disp (cc)	Engine type	Dry Weight*
40 EFI	995	Inline 4	112 kg
40 Pro EFI	995	Inline 4	118 kg

*Lightest model available

HP	Disp (cc)	Engine type	Dry Weight*
40 EFI	747	Inline 3	98 kg
40 CARB	747	Inline 3	93 kg

*Lightest model available



25 / 40 / 65 / 80 Jet Outboard

Shallow-Water Champ

When the water's too shallow for propeller-driven boats, turn to a Mercury Marine Jet. Designed for extreme shallow-water operation.

A Mercury Jet outboard gets you to those hard-to-reach spots quickly and confidently, with a wide range of FourStrokes, from 25 to 80 hp, to match your needs.

- The engine and jet pump combines to produce big time propulsion. With no prop, no skeg, no snags.
- An electronic fuel injection system that delivers the power you need, right now. Less fuel, no smoke, no problem.
- Total control. Thanks to the optional centre-mount Mercury Big Tiller offered on the 40, 65 and 80 hp models. Steering, trim, shift and digital troll-control are in the palm of your hand.

GO WHERE OTHERS CANNOT

HP	Disp (cc)	Engine type	Dry Weight*
80 / 65 EFI	2064	Inline 4	165 kg
40 EFI	995	Inline 4	121 kg
25 EFI	526	Inline 3	84 kg

*Lightest model available





Jet advantages

Water is drawn into the unit through the intake grill by an impeller, driven directly by the engine driveshaft. The water is then forced at high pressure through an outlet nozzle, creating thrust that drives the boat forward. To obtain reverse, a gate lifts into position over the outlet re-directing the pressure stream in the opposite direction.

Because there is no lower unit extending below the hull, the jet drive permits passage over obstacles that would foul propeller-driven outboard boats.

Shallow water. Deep experience.

Shallow water can mean opportunity and adventure. But it can also mean damaged props. No props. No skegs. Impossible-to-reach places are well within your reach.





25 / 30 FourStroke

Dependable starts and performance

When the battery on an ordinary engine is drained, you have nowhere to go. Not so with a Mercury 25-30 hp FourStroke. Every engine in the horsepower range comes standard with a manual recoil starter. So even if the battery quits, you can take matters into your own hands and keep your boating trip going.

Battery-free Electronic Fuel Injection (EFI) on Mercury 25-30 hp FourStroke models delivers consistently easy starting, crisp throttle response, increased fuel economy and outstanding overall performance.

Step up to a 30 high output. 30 hp exclusive.

Nothing moves a big load better than a 747 cc displacement powerhead producing more thrust to power heavier loads, from a heavy boat to a large aluminium or fibreglass fishing boat, the Mercury 30 HO delivers the control, thrust and low speed control to make your boating experience as best as you can imagine.

IT STARTS WHEN YOU SAY SO

HP	Disp (cc)	Engine type	Dry Weight*
30 HO EFI	747	Inline 3	98 kg
30 EFI	526	Inline 3	78 kg
25 EFI	526	Inline 3	71 kg

*Lightest model available



Low end torque

These 25 - 30 hp FourStrokes may be small on horsepower, but they're big on displacement. Featuring loads of strong, low end torque, these outboards have the power needed to get you up on plane with immediate throttle response and quick acceleration.

Comes in handy

Thanks to the Mercury multifunction tiller handle, standard on 25 - 30 hp FourStroke models, you can cruise the water with one hand behind your back. This revolutionary, all-in-one handle design delivers one handed operation for shifting, stopping, throttle control, tilting, friction control and steering. Small car booths or storage areas, the 25 - 30 hp comes in handy again with a tiller that can fold all the way down for easy storage.

Great acceleration, more torque

Compact but powerful, Mercury 25 - 30 hp FourStroke outboards feature **extra displacement and outstanding low-end torque** that put a boat smartly on plane.

Single-handed control

The exclusive Mercury multifunction tiller handle puts **all-in-one control** in the palm of your hand - shifting, stopping, throttle control, tilting and steering (available on 526 cc models only).

Electrical support

A high-output alternator **keeps batteries charged** and fishing electronics humming.





15 / 20 FourStroke

Get more of everything

More power. More control. More comfort. The Mercury 20 hp and 15 hp FourStroke outboards are designed to improve every minute of your time on the water:

- Innovative adjustable tiller handle is designed for comfortable left- or right-hand operation.
- Electronic Fuel Injection (EFI) delivers quick starts and crisp throttle response.
- Twin-cylinder powerhead produces outstanding torque for great acceleration.
- Lightweight design offers enhanced portability and improved performance.
- Engine mounts keep vibration off the boat and tiller handle.
- Maintenance is made easy with no-drip oil changes.
- Ready for a wide range of applications; choose rope or electric starting, tiller or remote control, and up to three shaft-length options.

COMPACT SIZE, BOLD PERFORMANCE

HP	Disp (cc)	Engine type	Dry Weight*
20	333	Inline 2	45 kg
15	333	Inline 2	45 kg

*Lightest model available





Less weight, more torque


The low-friction single-overhead cam powerhead delivers greater torque. Meanwhile, overall weight is decreased by 4,5 kilos – a significant reduction that makes a big difference on small boats. More power and less weight improve on-plane performance and top speed. These are the quickest, fastest and strongest outboards in the category!

Easy, reliable starting

The FourStrokes' Electronic Fuel Injection (EFI) system doesn't require a battery for rope-pull starting. EFI also produces easy starts – hot or cold – and outstanding fuel efficiency. It self-adjusts to deliver peak performance according to weather and elevation. And most maintenance issues related to modern fuels are eliminated by the pressurized fuel system. Throttle response is always crisp.

Ambidextrous tiller

The centre-mounted tiller provides simple horizontal adjustment and reversible throttle grip rotation for port or starboard installation. Vertical down-stop is also adjustable, so you can dial in this tiller to fit the boat and the operator's reach and preference. The tiller locks up at 45 or 73 degrees for fishing or trailering. The large shift lever is located forward on the tiller for easy operation, and a knob on the tiller adjusts throttle friction.



The adjustable vertical down stop sets the tiller at a comfortable operating position.

The tiller vertical angle locks at 73 degrees to create more boat space for the driver.



15 ProKicker

Strong. Smooth. Precise. Reliable.

Get all the power you need to control bigger boats. Electronic Fuel Injection (EFI) enables precise fuel metering for smooth operation all day at the lowest trolling speeds.

The innovative adjustable tiller handle is designed for comfortable operation with port or starboard transom mounting. Lightweight design takes a load off your transom, and new engine mounts isolate vibration away from the boat and tiller handle.

POWER AND COMFORT

HP	Disp (cc)	Engine type	Dry Weight*
15 ProKicker	333	Inline 2	56 kg

*Lightest model available



Exclusive ProKicker features

- EFI delivers fast, reliable starting and controlled throttle response in all weather.
- Superior torque provides greater acceleration for better boat control.
- High-thrust four-blade Mercury propeller with added blade area and a low pitch efficiently transfers engine torque to the water – the perfect combination for controlling larger fishing boats under most conditions.
- Standard power tilt gets you up and running fast with no reach, no bending over.
- Exclusive centring straps automatically straighten and lock the outboard in place when tilted up to protect the clamp bracket during high-speed runs and trailering.
- 9-amp alternator output at trolling speeds helps keep batteries charged.

Ambidextrous tiller

The new centre-mounted tiller provides simple horizontal adjustment and reversible throttle grip rotation for port or starboard installation. Vertical down-stop is also adjustable, so you can dial in this tiller to fit the boat and the operator's reach and preference. The tiller locks up at 45 or 73 degrees for fishing or trailering. The large shift lever is located forward on the tiller for easy operation, and a new knob on the tiller adjusts throttle friction.

Easiest to drive

- Innovative adjustable tiller handle is designed for comfortable left- or right-hand operation.
- Electronic Fuel Injection (EFI) delivers quick starts and crisp throttle response.
- New twin-cylinder powerhead produces outstanding torque for great acceleration.
- Lightweight design offers enhanced portability and improved performance.
- New engine mounts keep vibration off the boat and tiller handle.
- Maintenance is made easy with no-drip oil changes.
- Ready for a wide range of applications; choose rope or electric starting, tiller or remote control, and up to three shaft-length options.





8/9.9 FourStroke

Still the lightest in their class

Mercury's 8-9.9hp FourStrokes are still the lightest in their class, but being lightweight doesn't mean cutting corners. Our 8-9.9hp FourStrokes feature a convenient multifunction tiller handle that provides easy one-hand shifting operation. Furthermore, these outboards come equipped with our exclusive automatic reverse hooks that don't require you to change a clumsy lever manually to hold the engine in place while reversing.

Thanks to the Mercury multifunction tiller handle, standard on 8-9.9hp tiller handle FourStroke models, you have the boat control needed to fish all day with ease. This revolutionary, all-in-one handle design delivers one-handed operation for shifting, stopping, throttle control, tilting and steering. Giving you unrivaled manoeuvrability and making your time on the water easier and more enjoyable.

The 8-9.9hp Mercury FourStrokes feature an ingenious design that allows the boater to use the longer, sturdy tiller handle to gain leverage on the outboard and engage our exclusive 3-position ratcheting trim system. By pushing down on the tiller handle you can set the trim position. Simply, easily, every time.

LIGHT ON WEIGHT, HEAVY ON FEATURES

HP	Disp (cc)	Engine type	Dry Weight*
9.9	208	InLine 2	38 kg
9.9 CT	208	InLine 2	40 kg
8	208	InLine 2	38 kg

*Lightest model available



Total tiller control

Tiller-steered versions feature the exclusive Mercury **multifunction tiller** that puts shifting, throttle control (with friction for fine-tuned trolling), stopping, tilting and steering in the palm of your hand.

Reliable starts

A refined fuel system delivers consistent, easy and reliable starting quality and operation. Enhancements have also been made to the cold starting procedure by incorporating a three-position choke system and an ignition timing change improved trolling speed operation.

Defining durability

The gearcase is engineered to be rugged and durable, with **robust gears and bearings** and a **heavy-duty skeg**.

Power tilt

The fastest power tilt in the industry drops a Mercury 9.9hp FourStroke outboard into the water in just five seconds. Exclusive centring straps (optional) align and secure the outboard in full tilt-up position while you're underway.

More thrust

Mercury Command Thrust outboards feature a deeper gearcase and a four-blade, high-thrust propeller with matching gear ratio – the perfect setup for trolling and precise control in all conditions.



2.5 / 3.5 / 4 / 5 / 6 FourStroke



Being light and affordable isn't the whole story

For outboard engines in this horsepower range, portability is key and Mercury's 2.5-6 hp FourStrokes are among the lightest outboards in this class. Every Mercury portable FourStroke is packed full of features, such as our automatic reverse locking system to our convenient integral fuel tanks. These FourStrokes undergo the same corrosion resistance processes used in our higher horsepower products.

These small outboards are packed with big features. From multi trim and shallow water positions (on our 4-5-6 models) to tillers with 360 degree steering (on our 2.5-3.5 hp models), you'll find the performance and versatility you need to meet any situation. Starting is easy, thanks to automatic decompression, which bleeds off cylinder pressure during start up, requiring less pulling force to start the engine.

With their low weight and conveniently positioned large grip carrying handles, getting the power to your boat is not a problem. And because these lightweight outboards are subject to our rigorous testing standards, you get the same reliability as you expect from every Mercury outboards.

THE LIGHTWEIGHT CHAMPIONS

HP	Disp (cc)	Engine type	Dry Weight*
6	123	1	25 kg
5 Sail Power	123	1	27 kg
5	123	1	25 kg
4	123	1	25 kg
2.5 / 3.5	85	1	18 kg

*Lightest model available



Precise control

Mercury 2.5 and 3.5 hp FourStroke engines feature neutral-forward shifting with 360-degree steering for full thrust in all directions.

Easy to start

Automatic decompression bleeds off cylinder pressure to reduce the pulling force required to start the engine.

Shallow water

Multiple trim positions enhance performance and enable shallow-water operation.

Portability with ease

Mercury's 4-5-6 hp FourStrokes all features standard integral fuel tank with an external fuel shut off valve and the ability to connect an optional remote fuel tank. An integral fuel tank means you don't have to connect the outboard with another fuel tank on the boat, but for the marathon boaters an optional remote fuel tank can be connected in a split second.



**NEW**

5 Propane FourStroke

Powerful, Convenient And Eco-Friendly

Mercury's new 5hp FourStroke Propane outboard provides more convenience and less hassle. Now you can power your boat with the same propane used for your grill and eliminate the need to haul gasoline.

The 5hp FourStroke Propane outboard with a large 123cc displacement offers best-in-class power by delivering a true 5hp – something our competition can't claim.

Sail Power

Sail Power models are designed for sailboats and feature an alternator and more thrust to control larger boats.

10 Hours of boating on 9 kg standard Propane tank

(Approximate operating time at 5,000 rpm)

E C O - F R I E N D L Y

HP	Disp (cc)	Engine type	Dry Weight*
5	123	1	27,2 kg
5 Sail Power	123	1	28,6 kg

*Lightest model available

NOTE: Please contact your local dealer to check if this engine is be available in your country or region.





Reliability, Portability and Power with the convenience of Propane

- Runs on conventional propane, a convenient alternative to gasoline
- Eco-friendly and clean-burning with 30% lower exhaust emissions compared to gasoline
- Auto propane-shutoff valve on outboard for safety
- Light and portable, starting at just 27 kg
- No fuel priming required
- Manual choke for fast, reliable starts
- Easy-to-reach shift lever

Choke for fast and easy starts

The manual choke enriches the fuel-to-air ratio, delivering fast and easy starts, particularly when the engine is cold.

Easy and safe fuel hose connection

Fuel hose connector threads quickly and easily to the outboard and contains a shut-off valve to safely stop the flow of propane when disconnected.

Features

- 12 Volt, 4 Amp / 50-Watt charging system with cable to charge battery or other electronics
- Reverse-thrust exhaust relief hole
- 6-inch high-thrust propeller





D I A L E D - I N P E R F O R M A N C E





Pro XS

Extraordinary engineering for extraordinary speed

High-performance features unite to get you there first:

- Lightning-quick acceleration
- Blazing top speed
- Steadfast dependability
- Quiet operation that belies its true power
- A foundation of Mercury Racing heritage

Mercury ProXS outboards from 115hp to 300hp are engineered for the most-demanding people on the water – anglers battling on the tournament trail and powerboaters who crave speed and acceleration. Mercury developed exclusive components and tuning to extract every ounce of performance from each ProXS model.



175 / 200 / 225 / 250 / 300 Pro XS

Winning acceleration

No outboard gets from zero to wide-open quicker than a Mercury Pro XS, now with V-8 4.6-litre and V-6 3.4-litre muscle. This is performance that will rocket your rig out of the hole and to the next hot spot in record time. These Pro XS models feature generous displacement in a performance-tuned powerhead with a deep-breathing double-overhead-cam design and long-runner intake tract that delivers instant throttle response at any speed.

More displacement delivers more torque, and new Transient Spark technology optimizes spark timing to boost that torque during hole shot with a 1.75:1 gear ratio and a robust 3.2-centimeter-diameter prop shaft is designed for semi-surfacing, high-speed applications. Specific performance calibration takes rpm to 6200 at wide-open throttle for more flexible prop selection.

Squeezing speed from fuel

Mercury V-8 and V-6 Pro XS models transform every drop of fuel into performance to deliver excellent economy at cruising speed and wide-open throttle. Advanced Range Optimization (ARO) calibration utilizes closed-loop fuel control to precisely adjust the fuel mixture and deliver the best possible efficiency.

TAKE IT TO THE LIMIT

HP	Disp (cc)	Engine type	Dry Weight*
300	4600	V-8	229 kg
250	4600	V-8	229 kg
225	4600	V-8	229 kg
200	4600	V-8	229 kg
175	3400	V-6	213 kg

*Lightest model available





Never run out of juice

A powerful alternator provides net charging output of 20 amps at idle and 85 amps total at wide open throttle. Additionally, Idle Charge battery-management technology automatically increases idle rpm to boost alternator output and recharge low batteries to the proper level.



The cowl stays on

For easy oil checks and fills just pop open the new watertight Service Door on top of the cowl. Even smarter, at start-up the optional electronic oil-level sensor automatically alerts you to low oil level.





115 / 150 Pro XS

When going fast matters most

The Mercury 115 Pro XS delivers significantly better performance than any other high-output 115hp outboard on the market today. In fact, the 115 Pro XS is lighter than the nearest competing 115hp engine. Its 2.1L displacement is higher than that of any competing 115hp engine. This unbeatable combination delivers higher torque, better performance and greater durability.

Meet the boss of the 150hp high-output class. The Mercury 150 ProXS is tuned to take mid-size boats to the limit. A 3.0-litre powerhead offers the most displacement – yet the lowest weight in the 150hp category – and acceleration-boosting Transient Spark for heightened performance. Down below is a durable and proven 4.8-inch gearcase with four front water pickups on the nose of the torpedo. That provides more flexibility to mount the engine higher, install a jack plate, or trim more aggressively to maximize top-speed performance.

Additional advantages on both 115 and all ProXS include:

- Stiff high-performance motor mounts for better high-speed handling and feel
- Untouchable hole shot
- Superior battery management

HIT THROTTLE, HOLD ON, WIN

HP	Disp (cc)	Engine type	Dry Weight*
150	3000	Inline 4	207 kg
115 CT	2064	Inline 4	165 kg
115	2064	Inline 4	163 kg

**Lightest model available*



Best-in-class acceleration

Optimized spark timing to boost torque during acceleration for better torque at the prop shaft. The lowest weight and most displacement in the category also contribute to unmatched hole shot on a wide variety of boats.

High-performance calibration

Higher wide-open-throttle rpm range permits the use of a wider selection of prop pitches, so you can prop for hole shot or top speed.

Smart charging

High ampere alternator keeps up with electronics, lights, aerator pumps and audio systems. Idle Charge low-voltage battery-management automatically boosts idle speed and alternator output to recharge boat batteries to the proper level.





RACE INSPIRED PERFORMANCE



Mercury Racing

The Race Never Stops!

How do you improve in a category that's already fiercely strong? By creating new levels of performance, efficiency and reliability. Our line of outboards springs from a heritage of uncompromising breakthroughs. We continue to set the bar ridiculously high. Because you want it. Because we demand it.

For us, innovation isn't optional. The minute we finish an engine is the minute we start engineering its replacement. It's more than tweaking the drive or increasing the horses. It's about starting a revolution. We don't just aim to outperform our competitors – we aim to outperform ourselves.



250R/300R

Power. Like you've never felt it before.

The 300R FourStroke is the highest performing engine in its class. The naturally aspirated 4.6 L V-8 provides an astounding 44% in increased displacement and up to 40% higher overall bottom end torque than the legacy two-stroke 300XS it replaces.

The 250R FourStroke pumps out 250 propshaft horsepower. The stout V-8 powerhead provides an astounding 53% increased displacement and up to 40% higher overall bottom-end torque than the legacy two-stroke 250XS it replaces.

Designed, developed and manufactured in-house, the naturally aspirated, 4.6 L V-8 fourstroke engines share Mercury Racing's venerable Quad Cam Four Valve (QC4) sterndrive DNA – complete with aluminium four-valve cylinder heads and dual overhead camshaft (DOHC) valve train. The four valve heads and DOHC valve train are integrated with Mercury's proprietary V-8 cylinder block, packed with high performance hardware.

Colour options

An optional Graphite Grey accent panel is available as a kit. A paint-ready kit is also available to custom match the engine to the boat.



POWERFUL. FAST. EFFICIENT.

HP	Disp (cc)	Engine type	Dry Weight*
300	4600	V-8	232 kg
250	4600	V-8	236 kg

**Lightest model available.*



Unmatched torque

Mercury's proprietary transient spark calibration, which boosts torque by as much as 7% during hole shot by optimizing spark timing and fuelling, gets boats on plane quickly.

...all that displacement and power are delivered in a compact light weight package with 66-centimeter mounting centres, perfect for repower and multi-engine options.

Bold new styling

Aggressively styled top cowl designates a new era of high performance outboard propulsion from Mercury Racing. Bold new, ultra-premium graphics with Devil Red accent panel screams performance.



The cowl stays on

For easy oil checks and fills just pop open the new watertight Service Door on top of the cowl. Even smarter, at start-up the optional electronic oil-level sensor automatically alerts you to low oil level.

Verado 400R

Class leading performance

Born out of a passion for perfection, the Mercury Racing Verado 400R ups the ante in outboard engine performance. Serious enhancements have been made to the proven 2.6L supercharged dual overhead cam platform, delivering incredible achievements in power and efficiency. A 7,000 RPM rev limit for blistering acceleration, custom Mercury Racing calibration and impressive power-to-weight ratio are just the beginning of the advancements the 400R delivers. This engine isn't for the faint of heart and has been engineered specifically for lightweight high performance hulls that have 1 goal in mind - SPEED. Do you have the need?

Colour options

The Mercury 400R is offered in Phantom Black or Cold Fusion White. Six different colours (Blue, Green, Orange, Purple, Red and Yellow) are available for the graphics package on the Cold Fusion White 400R and are designed to reflect your personal style or match the colour palette of the boat. Either way, heads will turn, even if you won't be in view for long.



PERFORMANCE ABOVE ALL ELSE

HP	Disp (cc)	Engine type	Dry Weight*
400	2600	Inline 6	303 kg

*Lightest model available





Brains behind the brawn

A big part of what makes the 400R so great is the suite of technologies that support the Verado platform. SmartCraft integrated marine technology is the brains behind the operation and the backbone for leading technologies like Digital Throttle & Shift and Joystick Piloting for Outboards. SmartCraft links the engine, controls, steering, and displays to provide data to keep the user informed of engine diagnostics and performance.

Supercharger

The water-cooled supercharger uses the engine cooling system to reduce air temperatures and supercharger load, increasing supercharger durability and more importantly – POWER

Cool air intake

The cool air intake grabs fresh outside air to feed the supercharger and cooler air means more horsepower for big performance gains.

For even more power, the air is cooled one last time by the charge air cooler after the air exits the supercharger and before it enters the cylinder head for maximum performance.

NEW
450R

Run wide open, without compromise.

Handcrafted by Mercury Racing for the high-performance disciple craving unrelenting power, the Mercury Racing 450R makes the paramount performance statement. Boosted by an exclusive Mercury Racing supercharger, the 4.6-liter V-8 FourStroke powerhead delivers 450 peak horsepower while staying considerably lighter than the nearest competitor. Run wide open, without compromise.

The 450R writes a power prescription that combines unprecedented acceleration and top speed potential with rugged reliability and the latest technology from Mercury Racing. Multiple gearcase, control system, tie bar, and styling options are available to create the ultimate customized outboard performance package, ready to run Wide Open all day long. Best of all, the Mercury Racing 450R delivers all of its performance on readily available 95 RON pump fuel.



GO FARTHER, FASTER.

HP	Disp (cc)	Engine type	Dry Weight*
450R 5.44 HD	4600	V-8	313kg
450R SPORT MASTER	4600	V-8	318kg

*Lightest model available.





V-8 / 4.6 L / Transient Spark

V-8 / 4.6 L / Transient Spark Experience performance delivered with refined authority. Class-leading 4.6-liter displacement and a proprietary V-8 architecture are enhanced by the Mercury Racing Quad Cam Four Valve (QC4) design with double overhead camshafts and aluminium cylinder heads that maximize airflow and power. Mercury Transient Spark Technology applies preprogrammed timing advance to optimize torque output for stronger hole-shot performance. Power density is a key to high performance, and no marine engine delivers more punch in a lighter package than a Mercury Racing V-8 outboard. Every ounce is devoted to Wide Open exhilaration.



Advanced MidSection Integrated Tie Bar Power Steering

Each gram has been examined to reach to achieve maximal power with minimal weight. The Mercury Racing Advanced MidSection (AMS) features heavy-duty guide plates and stiffened engine mounts to stabilize the outboard for enhanced high-speed handling.

The AMS also isolates the powerhead from the transom to ensure run quality is smooth and quiet at all speeds. An optional rear tie-bar bracket integral to the AMS provides a strong, ultra-light mounting point and uncluttered installation for catamaran and other high-speed applications.

The 450R is offered with a choice of the HD gearcase for traditional, submerged applications or, for boats capable of speeds over 136 km/h, the surface-piercing Sport Master gearcase with a new one-piece stainless steel propshaft.

Rugged Midsection Corrosion Protection 3-Year Warranty

Mercury Racing V-8 outboards are engineered to be reliable and durable. These high-performance outboards are tested, tested and tested again – in the lab and on the water – in a never-ending quest to exceed the highest expectations. Run wide open with confidence.

Colour options

The Mercury Racing 450R is available in Cold Fusion White and the legendary Mercury Phantom Black. Cold Fusion White models are finished with Devil Red Eye cowl accent panels and white Advanced MidSection (AMS) and gearcase. Black models are finished with Graphite Gray cowl accent panels and matching Graphite Gray AMS and gearcase. Devil Red Eye, Graphite Gray and Carbon Fiber accent panel kits are available to custom-match a 450R outboard to a boat color scheme.

Graphite Gray

Devil Red Eye

Carbon Fiber





Supercharger Charge-Air Coolers Boost Bypass

Mercury Racing applies its supercharging expertise to extract incredible power from the 4.6-liter V-8. A 2.4-liter twin-screw supercharger delivers pressurized ambient air to the intake tract for instant throttle response. The supercharger is water-cooled to reduce the temperature of the intake charge and increase power. A boost bypass valve automatically adjusts maximum boost pressure to maintain peak performance in response to changing ambient conditions. A custom-designed attenuator is tuned to cancel the harshest high-frequency supercharger noise.

The Mercury Racing 450R is fitted with a special high-capacity oil cooler and an exclusive poppet valve in the midsection to provide a higher volume of cooling-water flow on-demand. The valve train features a high-performance intake camshaft and race-spec Inconel exhaust valves. Wide-open throttle (WOT) operating range is extended to 5800-6400 rpm to expand propping options and maximize performance.





HIGHEST QUALITY PARTS



Industry-Leading Protection

Parts and Accessories

After taking a severe beating from rough waves, high levels of moisture and an extremely high throttle output, your marine engine requires scheduled care available from our genuine parts and accessories. With so many moving parts, your outboard lives on proven performance oils and lubricants specially designed by our experienced and knowledgeable engineers.



The right engineering

A world-class engine should be maintained with world-class parts. Mercury Precision Parts® and Quicksilver Marine Parts & Accessories® are original parts and accessories, so they keep your engine within its original specifications. They should – they're designed by the same people who design Mercury engines.

Pay attention to your engine safety!

Use only genuine parts and accessories, because only Mercury and Quicksilver grant you reliability and full efficiency, this is the original parts strenght!

The materials employed are exclusively developed for Mercury engines. Our lubricants, accessories, spare parts and propellers are the right choice for each engine.



Tested & Proven

Component samples are drawn from the assembly line and checked to ensure conformity with the original design.

All outboards are extensively tested in the engineering lab where technicians can monitor all engine vital signs and performance.

Why using genuine Mercury and Quicksilver Service Parts?

- All Genuine parts are manufactured according the same high quality standards and are rigorously tested during many hours while after market parts are simply replicated!
- To succeed testing, the usage of superior materials is required assuring the ultimate in reliability.
- Genuine Service Parts are specifically engineered for marine applications. Load and heat in a marine environment is different from automotive and requires more robust part specifications.
- Use Genuine Service Parts to ensure your Mercury outboard performs to a high quality without voiding the warranty.
- Genuine parts contribute to maintaining your Mercury engine's used market value.



Oils & Lubricants

Our specialized oils and lubricants are manufactured to give any outboard the best performance, making Quicksilver Lubricants your only choice during scheduled maintenance.

#1 Marine Oil on the Market:

- 5 years of Engineering and development.
- Ultimate wear protection keeps cams and other engine parts looking and operating as new for longer.
- Recommended for more engines on the market than any other 4-stroke oil.
- Quicksilver is 34% stronger than FC-W minimum requirement.
- Approved by Mercury Marine engineers and meets warranty requirements.

Recommended Quicksilver TwoStroke Oils

	2.5 hp - 30 hp*	40 hp - 115 hp*	Above 115 hp*	All hp Direct Injection
Premium	★★	★★	-	-
Premium Plus	★★★	★★★	★★★	★★★
OptiMax/DFI Oil	★★★★	★★★★	★★★★	★★★★

* CARBureted or EFI

Recommended Quicksilver FourStroke Oils

	2.5 hp - 30 hp*	40 hp - 115 hp*	Above 115 hp*	Verado
25W40	★★★	★★★	★★★	★★★
25W40 Synthetic Blend	★★★★	★★★★	★★★★	★★★★

NOTE: 10W30 is recommended in operating temperatures for use below 4°C (40°F) for outboards (except Verado) and outboard 30 hp and below with manual start.

Better Control

Outboard Gearcases

All that power. It won't get you anywhere without a properly designed gearcase. One that fits your boat and engine properly. In addition to the gearcases that come standard with your outboard, Mercury has engineered specialized gearcase options to fit unique boat application and performance needs. Whatever Mercury outboard you're running, rest assured you'll have the perfect performance-matched gearcase that gets the most out of your outboard.



Standard

The standard bearer. Specifically designed to leverage the hydrodynamic engineering expertise that ensures that the horsepower your Mercury outboard creates is efficiently transferred to the propeller, providing you the performance and fuel efficiency you come to expect from your engine.





Command Thrust

The larger Command Thrust "CT" gearcase with a bigger-diameter propeller lifts heavy boats onto plane more easily and holds them there at lower speeds without impacting top speed.



Heavy Duty (HD)

Perfect for more aggressive go-fast boats and commercial offshore applications that operate in rough seas or want that extra mile per hour. We pair our Offshore 5.44-inch gearcase with a 1.75 gear ratio and 1.25-inch prop shaft for added durability.



Torque Master II

The Torque Master II gearcase is designed specifically for performance bass boats with top speeds of up to 85 mph. Its stout 1.25-inch prop shaft can handle the strain of running at an elevated mounting height. Patented front water pickups keep the engine running cool regardless of engine height. A cambered skeg improves handling and drivability.



Sport Master

Sport Master Gearcase offers heavy-duty durability for boats that travel in excess of 85mph (74 knots). The Sport Master gearcase is equipped with low-water pick-ups and a crescent leading-edge torpedo design that maximizes efficiency.



PREMIUM PROPELLERS



Perfecting propulsion



Mercury Propellers

Mercury propellers are produced by an engineering crew with more than 160 years of combined experience and a manufacturing team dedicated to perfection. Mercury uses proprietary and patented metals to design and build propellers for best-in-class performance and fuel-efficiency improvements.

Mercury recently introduced a four-blade propeller that generates enough lift to outrun its three-blade counterparts, and a hub system that significantly decreases shift noise and vibration for a better boating experience.

Prop selection can impact virtually every aspect of your boat's performance, and Mercury has a solution for every propeller challenge. It's no wonder you see Mercury propellers on boats of all engine brands.

Comp and Performance Series

Unmatched performance. Mercury's Comp and Performance Series propellers stand alone in the market as the top-performing propellers in acceleration, top speed and fuel economy.



REVOLUTION 4®

- Aggressive four-blade design provides outstanding holding, hole shot and improved midrange performance.
- Ideal for 135 hp and above outboard-powered walleye boats, centre consoles and sport boats.



ENERTIA®

- Mercury's first propeller to utilize the added strength and durability of Mercury's X7 alloy.
- Improves both top speed and acceleration.
- Fits 135 hp and above outboards.



ENERTIA ECO® / XP*

- Designed for heavy, high-horsepower boats where fuel economy at cruise is top priority.
- Large-diameter propeller with high-progressive rake providing extra bow lift, resulting in up to 10 % fuel economy gains at cruising speeds.



MAX5® / ST*

- The Lab Finished MAX 5 provides a measurable reduction in propeller slip, (up to 12%).
- New 15.25-inch diameter models offer 3-4% reduction in slip compared to the 15.00-inch models on select outboard



FURY®

- Mercury's revolutionary tournament bass propeller.
- Comprised of Mercury's X7 alloy with a reduced diameter and large blade area that measurably improves acceleration and top speed.
- Designed for class-leading performance for all bass, bay and flats boats running 200 hp and above engines.



FURY 4®

- Mercury's high performance tournament load bass propeller.
- Manufactured with Mercury's X7 alloy for extreme durability.
- Designed for unmatched performance for the angler running heavily weighted 20 - 22' bass boats.



BRAVO I® / FS / LT / XS / OC / XC*

- The world's best-selling high-performance propeller.
- Ideal fit for high-speed, high-drive-height outboard.
- Provides outstanding performance for all 'go-fast' boats, including catamarans and stepped hulls.



5-BLADE CNC CLEAVER®*

- Designed to maximize top-end speed on performance hulls.
- Quarter-inch diameter and half-inch pitch increments for precise tuning.
- The CNC propeller makes the most of the Sport Master gearcase and elevated engine heights.

* Mercury Racing props are designed to maximize boat performance and handling in any application. Seek advice from your Mercury dealer.

Elite Series

Where performance meets reputation. Mercury's Elite Series propellers provide class-leading durability and performance. These are our best-selling designs.



SPITFIRE X7®

- Superior acceleration generated through a small diameter design.
- Ultimate top speed and holding through aggressive cup.
- Designed for all boat types utilizing Mercury's 75-115 hp standard outboards.



HIGH FIVE®

- Five-blade stainless steel design offers ultimate hole shot and handling.
- Perfect propeller for supreme tow sport performance
- Fits 135 hp and above outboards.




MIRAGE® PLUS

- Best-selling high-horsepower propeller in the world.
- Large diameter design works well across a wide range of applications.
- Fits 135hp and above outboard.



SPITFIRE®

- Mercury's state-of-the-art aluminium propeller provides three-blade speed with four-blade holding and acceleration.
- Aggressive four-blade design with high rake angles and added cup for tenacious holding.
- Fits 25 - 250 hp outboards.



TEMPEST® PLUS

- Designed to make big boats go fast.
- Higher rake and bigger cup provide better handling and lift on big V-6 outboard-powered boats.
- Ideal for 135 hp and above outboard-powered bass and tournament walleye boats 5 meters and longer.



TROPHY® PLUS

- Designed to deliver exceptional bow lift for bass and flats boats running at high drive heights.
- Unique design allows for venting both through and over the hub, providing quick holeshot and stable handling at high speeds and tight turns.
- Fits 135hp and above outboards.



TROPHY® SPORT

- High-performance propeller for bay and flats boats utilizing 40 - 60 hp outboards.
- Four-blade design generates incredible hole shot and holding when compared to a three-blade propeller.

Sport Series

Perfect balance of performance and value. Mercury's Sport Series propellers are proven designs for boaters ready to enhance the performance of their boat.



BLACK MAX®

- World's best selling aluminum propeller.
- Perfect combination of performance, durability and value.
- Fits outboards 2.5 - 250 hp.



LASER II

- Perfect compliment to bass boats and aluminium deep-v fishing boats where speed is the priority.
- Aggressive rake angles provide excellent bow lift with vented hub for impressive acceleration.
- Fits 75 - 125 hp outboards.



VENGEANCE®

- All-purpose stainless steel propeller offers improved performance and durability over aluminium propellers.
- One-piece cast steel for exceptional strength and durability.
- Fits 20 - 250 hp outboards.



VENSURE®

- Stainless steel four-blade design delivers good acceleration and holding power.
- Provides great bow lift for rough water performance.
- Fits 135 hp and above outboards.

Find the perfect prop

Follow five easy steps on the Mercury Prop Selector to find the ideal prop options for your boat and conditions.



Try it now at:
[MercuryMarine.com/propellers](https://www.MercuryMarine.com/propellers)





X7 Alloy

A revolutionary proprietary alloy from Mercury that shatters the rules of propeller design X7 is 30 percent stronger and four times more durable than conventional stainless steel, allowing prop designs that are impossible with conventional stainless steel.



Merccalloy®

An aluminium alloy so revolutionary – it's patented. Merccalloy is specially designed for the die-casting process, helping produce the highest quality, porosity-free propeller castings that result in increased strength and ductility.

Flo-Torq SSR HD

The Flo-Torq SSR HD is the quietest and smoothest shifting propeller hub system in the market for high horse-powered outboards. It delivers a 10-19% shift clunk improvement vs. other noise reduction rubber hub systems and a 25 %+ improvement vs. solid hub designs. The Flo-Torq SSR HD rotates both port and starboard - eliminating shift clunk and vibration for quiet and smooth shifting.



PVS® Plugs

PVS (Performance Vent System) is an exclusive Mercury innovation that allows you to custom- tune the venting of your propeller – this gives you the power to customize the performance of your propeller to match your engine. Just by varying the size of the exhaust hole, you can improve your performance. This is a system you can only get with select Mercury propellers.



Flo-Torq® Hub System

The Flo-Torq II is specially designed to cushion and protect the drivetrain from most impacts. Plus, just like all Mercury® engines, the Flo-Torq II System also provides unmatched corrosion protection – giving you peace of mind and the freedom to make the most of your time on the water.



Boldly do
what makes
you happy

Mercury Controls & Rigging

Selecting the best engine for your boat is the first step: Adding the appropriate controls and rigging not only makes boating easier, it delivers the best experience your boat and engine can provide. Controls and rigging are the displays you read and the instruments you use to start, stop, go and manoeuvre – everything that puts control of your boat in your hands. Mercury’s controls and rigging are integral elements of the “connected Mercury system” that extends past our core products to deliver aesthetically pleasing, technologically advanced, and user-friendly prop-to-helm solutions.



INTUITIVE DESIGNS





Mercury VesselView®

Mercury® VesselView® allows you to display engine information, genset, sounder, and much more. It has more information and data on boat and engine functions than any other system in the boating industry: rpm, speed, fuel flow and efficiency, temperature, trim, and more. You can monitor up to four engines at a time on an intuitive, "at a glance" LCD screen.

Mercury VesselView screens (903/703/502/403) integrate an Active Trim interface so that the Active Trim dash pad is not required.

VesselView® Mobile

VesselView Mobile allows you to use your mobile device (smartphone or tablet, Android or iPhone) to connect with your Mercury outboard or sterndrive engine. The plug-and-play module connects to your device via Bluetooth, providing quick, convenient access to your engine's data. One module can monitor up to six engines. You can even customize the data viewed across three screens to fit your boating style.

The product is compatible with all Mercury SmartCraft-capable engines 40 hp and above built since 2003. One module supports single through quad engine applications.



1st Mate

1st Mate™ adds another layer of boating safety by notifying a boat's captain or its passengers if someone has fallen overboard. 1st Mate also serves as an effective deterrent to boat-and engine theft. With 1st Mate, you can unlock the vessel via proximity of the captain's wearable and/or the "unlock function" of the app.

The 1st Mate system includes wearable wristband fobs or carabiners for the captain and up to seven passengers that sync with the 1st Mate app. App is used for account setup, system configuration and monitoring the status of the wearables

1st Mate is compatible with all Mercury SmartCraft engines 40 hp and higher manufactured since 2005.

Active Trim

This intuitive, hands-free system continually adjusts engine trim based on changes in boat speed to improve performance, fuel economy, and ease of operation. It responds to boat manoeuvres and speed changes with precision and delivers a better overall driving experience. No knowledge of trimming an engine is needed to take advantage of Active Trim.

Active Trim is compatible with all current SmartCraft-capable Mercury outboards and sterndrive engines (40 hp and above).



40 - 115hp Tiller

Mercury Marine's all-new 40 - 115hp Tiller introduces new-to-market features, functionality and innovative refinements that improve the customer's boating experience.

The tiller provides best-in-class right-hand and left-hand control, best-in-class tilt-lock system, intuitive touch points, and advanced styling and craftsmanship.

The user can easily lock the Tiller at broad 12°, 30°, or 55° angles with one hand while underway or stopped. Tilt locks provide stability and comfort.

The industry's first optional heated grip offers three levels of heat for cold-weather

operation. Anglers can warm their hands after handling their catch, and electronic features prevent excessive battery drain.

Troll Control comes standard and allows anglers to dial in precise trolling speeds by tapping a button to increase or decrease speed in 10-rpm increments. That's five times more precise than the competition's 50-rpm increments.





Joystick Piloting®

Forget complex. Forget stressful positioning or manoeuvring in tight spaces during less-than-ideal situations. Focus instead on a new feeling. One of total confidence. Confidence that comes from being effortlessly, intuitively, completely in control of your boat, thanks to the Mercury's Joystick Piloting system. The power to make your boat do exactly what you want, with just a touch of your fingertips. You don't have to be a control freak to appreciate that.

Digital Throttle and Shift

No cables, no hesitation, no maintenance. Zero shift and throttle effort. Instant response. Our SmartCraft Digital Throttle and Shift (DTS) delivers precise control and smooth operation to the outboard experience. Classic look, feel and ergonomics. Inspired by high-tech aircraft controls.



SC1000 and MercMonitor Gauges

The Mercury SC1000 and MercMonitor are the marine industry's most advanced gauges, offering essential vessel information along with advanced features such as Smart Tow, ECO, Troll Control and NMEA 2000 Gateway (gauge dependent). Mercury SmartCraft gauges provide instant, reliable information at a glance. Combined with additional sensors, Mercury's digital gauges are powerful tools to provide safety and comfort on the water.

Multi-colour LCD screen

Multi-colour LCD screen provides you with critical data on dozens of engine and boat functions. Temperature, depth, alarms, rpm, speed, water pressure, fuel flow, and much more. Perfect for a wide range of boats, both outboard and sterndrive, single- and multi-engine platforms. Program the data to match your needs and boating preferences. Select a colour to match your boat - or your mood.



Theft Deterrent System (TDS)

The Mercury Theft Deterrent System (TDS) improves boat and engine security. Simply plug the automotive-style key fob into the docking station on the helm and you're ready to go. The engine will start in guardian mode if the fob isn't present, but rpm is limited.

Moving Propeller Alert

The MP Alert system is the ideal safety choice to notify swimmers that a propeller is in motion. This system uses LED lights on the stern of the boat to alert swimmers that the propeller is moving.



S A T I S F A C T I O N

Satisfaction Guaranteed

Warranty and Protection

We know we build reliable engines. We know we make them easy and intuitive to use. We also know that few environments are more unpredictable than the marine environment. That's why if something goes wrong, we're right there with the most comprehensive warranty in the industry. It's our commitment to your satisfaction and our promise to you for putting your faith in us.



G U A R A N T E E D



World Class Engines, World Class Support

All recreational Mercury Outboard models from the 2.5 to 400hp range are eligible to 5 years of warranty* coverage for your peace of mind.

A comprehensive warranty that's supported by the strength and service expertise of one of the largest dealer networks. Simply have your engine serviced at a **Mercury Authorised Service Centre** at the recommended servicing intervals and you're covered by an additional up to 3-year factory backed warranty on top of the standard manufacturer's warranty.

Built to live in water

Mercury provides all pleasure craft engines limited corrosion protection for three full years. No matter whether you run in freshwater or saltwater, you're covered even in the harshest marine environments.

**Terms and conditions apply. Please check with your local Mercury Authorised Dealer for full warranty information or visit the "Service & Support" page on www.mercurymarine.com*




We go boldly in everything we do

In our sketches.

In our labs.


In our castings, machine shops
and aspirations.

We eat, breathe and live boldly. And we do it all for you. So you can go faster. Farther. Bolder. No matter what your day puts in front of you, our engines are always ready to push you toward your dreams and take you on the greatest experiences of your life.





YOUR PASSION FUELS OUR PASSION



Models ¹	450R 5.44 HD	450R Sport Master	400R Verado	400 Verado	350 Verado	300R	300 Pro XS	300 Verado	250R	250 Pro XS	250 Verado
Kilowatts ²	331	331	294	298	257	221	221	221	184	184	184
Max.RPM at Full Throttle	5800-6400	5800-6400	6400-7000	6200-6800	5800-6400	5800-6400	5600-6200	5200-6000	5600-6200	5600-6200	5200-6000
Cylinders	V-8	V-8	6 (in-line)	6 (in-line)	6 (in-line)	V-8	V-8	V-8	V-8	V-8	V-8
Smart Craft Compatible	Yes										
Displacement	4600 cc	4600 cc	2600 cc	2600 cc	2600 cc	4600 cc					
Starting	Electric										
Gear Ratio	1.60:1	1.60:1	1.75:1	1.75:1	1.75:1	1.75:1	1.75:1	1.85:1	1.75:1	1.75:1	1.85:1
Gear Shift	DTS	F-N-R	DTS	DTS							
Steering Midsection	AMS - EHPS	CMS - Remote	CMS - Remote	AMS - EHPS	CMS - Remote	CMS - Remote	AMS - EHPS - BTO				
Alternator System	85 amp (1071 W)	85 amp (1071 W)	70 amp (882 W)	70 amp (882 W)	70 amp (882 W)	85 amp (1071 W)	85 amp (1071 W)	115 amp (1449 W)	85 amp (1071 W)	85 amp (1071 W)	115 amp (1449 W)
Fuel System	Sci EFI	EFI	EFI	EFI	EFI	EFI	EFI				
Trim Positions	EHPT										
Fuel Tank	-	-	-	-	-	-	-	-	-	-	-
Fuel Requirements ³	UL95R/Up to 10 % ethanol										
Weight ⁴	313 kg	318 kg	303 kg	303 kg	303 kg	232 kg	229 kg	272 kg	236 kg	229 kg	272 kg
Available Boat Transom Heights	L - XL - XXL	L - XL	L - XL - XXL	L	L - XL	L - XL - XXL					
Counter Rotation	CL - CXL - CXXL	CXL	CL - CXL - CXXL	-	-	CXL - CXXL					

¹ Model offering may vary from one country to another. Please see your local dealer for specific information.

² Hp/KW measured at propshaft in accordance with ICOMIA 28.

³ 90RON compatible

⁴ Dry weight specification is for lightest model and excludes engine oil, rigging hardware and propeller.

GEAR SHIFTDTS: Digital Throttle and Shift • F-N-R: Mechanical Forward Neutral Reverse • F-N: Forward Neutral

STEERING MIDSECTIONAMS: Advanced Mid Section • CMS: Conventional Mid Section • EHPS: Electric Hydraulic Power Steering • BTO: Big Tiller Optional • RO: Remote Optional

ALTERNATOR SYSTEMESM: On Electric Start Models only • OPT: Optional • OPT: Optional 4 amp [50W] lighting, 2 amp [25W] charging • ML: ML Models only

FUEL SYSTEMEFI: Electronic Fuel Injection • Sci: Super Charge Injection • DFI: Direct Fuel Injection • CARB: through carburetor

TRIM SYSTEMEHPT: Electric Hydraulic Power Trim and Tilt • EHT: Electric Hydraulic Tilt (no Trim) • GAT: Gas assist trim • MTT: Manual Trim and Tilt • SWD: Shallow Water drive

FUEL TANKINT: Integrated fuel tank • RO: remote optional

AVAILABLE BOAT TRANSOM HEIGHTS381 mm [S] - 508 mm [L] - 635 mm [XL] - 762 mm [XXL]

COUNTER ROTATION508 mm [CL] - 508 mm [CL] - 635 mm [CXL] - 762 mm [CXXL]

Models ¹	225 Pro XS	225 EFI	200 Pro XS	200 EFI	175 Pro XS	175 EFI	150 Pro XS	150 EFI	115 Pro XS 115 Pro XS CT	115 EFI 115 EFI CT	100 EFI 100 EFI CT	80 EFI
Kilowatts ²	165	165	147	147	129	129	110	110	85	85	74	59
Max.RPM at Full Throttle	5600-6200	5200-6000	5600-6200	5000-5800	5400-6000	5000-5800	5200-6000	5000-5800	5300-6300	5000-6000	5000-6000	4500-5500
Cylinders	V-8	V-6	V-8	V-6	V-6	V-6	4 (in-line)	4 (in-line)	4 (in-line)	4 (in-line)	4 (in-line)	4 (in-line)
Smart Craft Compatible	Yes	Yes	Yes	Yes								
Displacement	4600 cc	3400 cc	4600 cc	3400 cc	3400 cc	3400 cc	3000 cc	3000 cc	2064 cc	2064 cc	2064 cc	2064 cc
Starting	Electric	Electric	Electric	Electric								
Gear Ratio	1.75:1	1.85:1	1.75:1	1.85:1	1.85:1	1.85:1	2.08:1	1.92:1	2.07:1 / 2.38:1	2.07:1 / 2.38:1	2.07:1 / 2.38:1	2.07:1
Gear Shift	DTS	DTS	DTS	DTS	DTS	DTS	F-N-R	F-N-R	F-N-R	F-N-R	F-N-R	F-N-R
Steering Midsection	CMS - Remote	CMS - Remote / BTO	Remote / BTO	Remote / BTO	Remote / BTO	Remote / BTO						
Alternator System	85 amp (1071 W)	60 amp (756 W)	60 amp (756 W)	35 amp (441 W)	35 amp (441 W)	35 amp (441 W)	35 amp (441 W)					
Fuel System	EFI	EFI	EFI	EFI								
Trim Positions	EHPT	EHPT	EHPT	EHPT								
Fuel Tank	-	-	-	-	-	-	-	-	-	-	-	-
Fuel Requirements ³	UL95R/Up to 10% ethanol	UL95R/Up to 10% ethanol	UL95R/Up to 10% ethanol	UL95R/Up to 10% ethanol								
Weight ⁴	229 kg	216 kg	229 kg	216 kg	213 kg	216 kg	207 kg	206 kg	163 kg / 165 kg	163 kg / 165 kg	163 kg / 165 kg	163 kg
Available Boat Transom Heights	L - XL	L - XL - XXL	L - XL	L - XL	L - XL	L						
Counter Rotation	-	CXL - CXXL	-	CXL	-	-	-	CXL	-	- / CXL	-	-

¹ Model offering may vary from one country to another. Please see your local dealer for specific information.

² Hp/KW measured at propshaft in accordance with ICOMIA 28.

³ 90RON compatible

⁴ Dry weight specification is for lightest model and excludes engine oil, rigging hardware and propeller.

GEAR SHIFT **DTS:** Digital Throttle and Shift • **F-N-R:** Mechanical Forward Neutral Reverse • **F-N:** Forward Neutral

STEERING MIDSECTION **AMS:** Advanced Mid Section • **CMS:** Conventional Mid Section • **EHPS:** Electric Hydraulic Power Steering • **BTO:** Big Tiller Optional • **RO:** Remote Optional

ALTERNATOR SYSTEM **ESM:** On Electric Start Models only • **OPT:** Optional • **OPT:** Optional 4 amp (50 W) lighting, 2 amp (25 W) charging • **ML:** ML Models only

FUEL SYSTEM **EFI:** Electronic Fuel Injection • **Sci:** Super Charge Injection • **DFI:** Direct Fuel Injection • **CARB:** through carburetor

TRIM SYSTEM **EHPT:** Electric Hydraulic Power Trim and Tilt • **EHT:** Electric Hydraulic Tilt (no Trim) • **GAT:** Gas assist trim • **MTT:** Manual Trim and Tilt • **SWD:** Shallow Water drive

FUEL TANK **INT:** Integrated fuel tank • **RO:** remote optional

AVAILABLE BOAT TRANSOM HEIGHTS 381 mm (S) - 508 mm (L) - 635 mm (XL) - 762 mm (XXL)

COUNTER ROTATION 508 mm (CL) - 635 mm (CXL) - 762 mm (CXXL)

Models ¹	60 EFI 60 EFI CT	50 EFI	40 EFI [4 cyl.]	40 EFI [3 cyl.]	40 PRO EFI	40 CARB	30 HO EFI	30 EFI	25 EFI	20 EFI	15 EFI ProKicker
Kilowatts ²	44	37	29.4	29.4	29.4	29.4	22.1	22.1	18.4	14.7	11.0
Max.RPM at Full Throttle	5500-6000	5500-6000	5500-6000	5500-6000	5500-6000	5500-6000	5000-6000	5250-6250	5000-6000	5700-6200	5700-6200
Cylinders	4 (in-line)	4 (in-line)	4 (in-line)	3 (in-line)	4 (in-line)	3 (in-line)	3 (in-line)	3 (in-line)	3 (in-line)	2 (in-line)	2 (in-line)
Smart Craft Compatible	Yes	Yes	Yes	Yes	Yes	Yes	-	-	-	-	-
Displacement	995 cc	995 cc	995 cc	747 cc	995 cc	747 cc	747cc	526 cc	526 cc	333 cc	333 cc
Starting	Electric	Electric	Electric	Electric	Electric	Manual	Manual and Electric	Manual and Electric	Manual and Electric	Manual or Electric	Manual
Gear Ratio	1.83:1 / 2.33:1	1.83:1	1.83:1	2.00:1	2.33:1	2.00:1	2.00:1	1.92:1	1.92:1	2.15:1	2.15:1
Gear Shift	F-N-R										
Steering Midsection	Remote / BTO	Remote / Tiller									
Alternator System	18 amp (226 W)	15 amp (186 W)	15 amp (186 W)	12 amp (145 W)	12 amp (145 W)						
Fuel System	EFI	EFI	EFI	EFI	EFI	CARB	EFI	EFI	EFI	EFI	EFI
Trim Positions	EHPT	EHPT	EHPT	EHPT or GAT	EHPT	GAT	EHPT	EHPT or GAT or MTT	EHPT or MTT	6 & SWD or EHT	6 & SWD or EHT
Fuel Tank	-	-	-	-	-	-	25 L	25 L	25 L	12 L	12 L
Fuel Requirements ³	UL95R/Up to 10 % ethanol										
Weight ⁴	112 kg / 118 kg	112 kg	112 kg	98 kg	118 kg	93 kg	98 kg	78 kg	71 kg	45 kg	56 kg
Available Boat Transom Heights	L	L	L	S - L	L	S - L	L	S - L - XL	S - L	S - L	S - L
Counter Rotation	-	-	-	-	-	-	-	-	-	-	-

¹ Model offering may vary from one country to another. Please see your local dealer for specific information.

² Hp/KW measured at propshaft in accordance with ICOMIA 28.

³ 90RON compatible

⁴ Dry weight specification is for lightest model and excludes engine oil, rigging hardware and propeller.

GEAR SHIFT **DTS:** Digital Throttle and Shift • **F-N-R:** Mechanical Forward Neutral Reverse • **F-N:** Forward Neutral

STEERING MIDSECTION **AMS:** Advanced Mid Section • **CMS:** Conventional Mid Section • **EHPS:** Electric Hydraulic Power Steering • **BTO:** Big Tiller Optional • **RO:** Remote Optional

ALTERNATOR SYSTEM **ESM:** On Electric Start Models only • **OPT:** Optional • **OPT:** Optional 4 amp [50W] lighting, 2 amp [25W] charging • **ML:** ML Models only

FUEL SYSTEM **EFI:** Electronic Fuel Injection • **Sci:** Super Charge Injection • **DFI:** Direct Fuel Injection • **CARB:** through carburetor

TRIM SYSTEM **EHPT:** Electric Hydraulic Power Trim and Tilt • **EHT:** Electric Hydraulic Tilt (no Trim) • **GAT:** Gas assist trim • **MTT:** Manual Trim and Tilt • **SWD:** Shallow Water drive

FUEL TANK **INT:** Integrated fuel tank • **RO:** remote optional

AVAILABLE BOAT TRANSOM HEIGHTS 381 mm [S] - 508 mm [L] - 635 mm [XL] - 762 mm [XXL]

COUNTER ROTATION 508 mm [CL] - 508 mm [CL] - 635 mm [CXL] - 762 mm [CXXL]

Models ¹	15 EFI	9.9 9.9 CT	8	6	5 Sail Power	5	5 Propane	5 Propane Sail Power	4	3.5	2.5
Kilowatts ²	11.0	7.3	5.9	4.4	3.7	3.7	3.7	3.7	2.9	2.6	1.8
Max.RPM at Full Throttle	5700-6200	5000-6000	5000-6000	5000-6000	4500-5500	4500-5500	5000-6000	5000-6000	4500-5500	5000-6000	4500-5500
Cylinders	2 (in-line)	2 (in-line)	2 (in-line)	1	1	1	1	1	1	1	1
Smart Craft Compatible	-	-	-	-	-	-	-	-	-	-	-
Displacement	333cc	208cc	208cc	123cc	123cc	123cc	123cc	123cc	123cc	85cc	85cc
Starting	Manual or Electric	Manual or Electric	Manual or Electric	Manual	Manual	Manual	Manual	Manual	Manual	Manual	Manual
Gear Ratio	2.15:1	2.08:1 / 2.42:1	2.08:1	2.15:1	2.15:1	2.15:1	2.15:1	2.15:1	2.15:1	2.15:1	2.15:1
Gear Shift	F-N-R	F-N-R	F-N-R	F-N-R	F-N-R	F-N-R	F-N-R	F-N-R	F-N-R	F-N	F-N
Steering Midsection	Tiller / Remote	Tiller / Remote	Tiller / Remote	Tiller / RO	Tiller / RO	Tiller / RO	Tiller	Tiller	Tiller / RO	Tiller	Tiller
Alternator System	12 amp (145W)	6 amp (76W) ESM	6 amp (76W) ESM	OPT	4 amp (50 W)	4 amp (50 W) ML	OPT	4 amp / 50 Watt	OPT	-	-
Fuel System	EFI	CARB	CARB	CARB	CARB	CARB	Propane Mixer	Propane Mixer	CARB	CARB	CARB
Trim Positions	6 & SWD or EHT	6 & SWD or EHT	6 & SWD	6 & SWD	6 & SWD	6 & SWD	6	6	6 & SWD	4	4
Fuel Tank	12L	12L	12L	1.1L INT - RO	1.1L INT - RO	1.1L INT - RO	Remote	Remote	1.1L INT - RO	1.1L INT	1.1L INT
Fuel Requirements ³	UL95R/Up to 10% ethanol	Propane	Propane	UL95R/Up to 10% ethanol	UL95R/Up to 10% ethanol	UL95R/Up to 10% ethanol					
Weight ⁴	45kg	38kg / 42kg	38kg	25kg	27kg	25kg	27.2kg	28.6k	25kg	18kg	18kg
Available Boat Transom Heights	S - L	S - L - XL	S - L	S - L	L	S - L - XL	S - L	L - XL	S - L	S - L	S
Counter Rotation	-	-	-	-	-	-	-	-	-	-	-

¹ Model offering may vary from one country to another. Please see your local dealer for specific information.
² Hp/KW measured at propshaft in accordance with ICOMIA 28.

³ 90RON compatible

⁴ Dry weight specification is for lightest model and excludes engine oil, rigging hardware and propeller.

GEAR SHIFT **DTS:** Digital Throttle and Shift • **F-N-R:** Mechanical Forward Neutral Reverse • **F-N:** Forward Neutral

STEERING MIDSECTION **AMS:** Advanced Mid Section • **CMS:** Conventional Mid Section • **EHPS:** Electric Hydraulic Power Steering • **BTO:** Big Tiller Optional • **RO:** Remote Optional

ALTERNATOR SYSTEM **ESM:** On Electric Start Models only • **OPT:** Optional • **OPT:** Optional 4 amp (50 W) lighting, 2 amp (25 W) charging • **ML:** ML Models only

FUEL SYSTEM **EFI:** Electronic Fuel Injection • **Sci:** Super Charge Injection • **DFI:** Direct Fuel Injection • **CARB:** through carburetor

TRIM SYSTEM **EHPT:** Electric Hydraulic Power Trim and Tilt • **EHT:** Electric Hydraulic Tilt (no Trim) • **GAT:** Gas assist trim • **MTT:** Manual Trim and Tilt • **SWD:** Shallow Water drive

FUEL TANK **INT:** Integrated fuel tank • **RO:** remote optional

AVAILABLE BOAT TRANSOM HEIGHTS 381 mm (S) - 508 mm (L) - 635 mm (XL) - 762 mm (XXL)

COUNTER ROTATION 508 mm (CL) - 635 mm (CXL) - 762 mm (CXXL)

Models ¹	80 EFI Jet	65 EFI Jet	40 EFI Jet	25 EFI Jet
Kilowatts ²	59	48	29.4	18.4
Max.RPM at Full Throttle	5000-6000	5000-6000	5000-6000	5000-5500
Cylinders	4 (in-line)	4 (in-line)	4 (in-line)	3 (in-line)
Smart Craft Compatible	Yes	Yes	Yes	-
Displacement	2064 cc	2064 cc	995 cc	526 cc
Starting	Electric	Electric	Electric	Manual and Electric
Gear Ratio	Jet drive	Jet drive	Jet drive	Jet drive
Gear Shift	F-N-R	F-N-R	F-N-R	F-N-R
Steering Midsection	Remote / BTO	Remote / BTO	Remote / BTO	Remote / Tiller
Alternator System	35 amp (441 W)	35 amp (441 W)	18 amp (226 W)	15 amp (186 W)
Fuel System	EFI	EFI	EFI	EFI
Trim Positions	EHPT	EHPT	GAT	GAT
Fuel Tank	-	-	-	25 L
Fuel Requirements ³	UL95R/Up to 10 % ethanol			
Weight ⁴	165 kg	165 kg	121 kg	84 kg
Available Boat Transom Heights	L	L	S	S
Counter Rotation	-	-	-	-

¹ Model offering may vary from one country to another. Please see your local dealer for specific information.

² Hp/KW measured at propshaft in accordance with ICOMIA 28.

³ 90RON compatible

⁴ Dry weight specification is for lightest model and excludes engine oil, rigging hardware and propeller.

GEAR SHIFT **F-N:** Forward Neutral

STEERING MIDSECTION **BTO:** Big Tiller Optional • **RO:** Remote Optional

FUEL SYSTEM **EFI:** Electronic Fuel Injection

TRIM SYSTEM **EHPT:** Electric Hydraulic Power Trim and Tilt • **GAT:** Gas assist trim


AVAILABLE BOAT TRANSOM HEIGHTS 381 mm (S) - 508 mm (L)



WELCOME TO THE MERCURY COLLECTION SHOP

Fan merchandise, shop equipment, customer or employee giveaways – whatever your reason for visiting: discover our brand-new selection of custom-made merchandising products and promotional articles from the brand world of Mercury Marine!

www.emea-mercuryshop.com





MERCURY *GO BOLDLY.™*

[MercuryMarine.com](https://www.MercuryMarine.com)



The quality system of
Brunswick Marine in EMEA
is ISO 9001 certified

© 2020 Brunswick Marine in EMEA. All Rights Reserved. Part #: 9M0102204

Brunswick Marine in EMEA continuously explores means to improve the products it designs, manufactures and distributes. Every effort is made to produce sales and service literature which is current. Changes to specifications of engines, boats and accessories are ongoing.

This brochure should not be regarded as a precise guide to the latest specifications. This brochure is also not an offer for sales of any particular engine, boat or accessory. Distributors and dealers are not agents of Brunswick Marine in EMEA or one of its affiliates and they have no authority to bind Brunswick Marine in EMEA by any express undertaking or representation, including but not limited to representations of product, sales, applications or service nature.

Not all products are available in all countries and some are available only in limited quantities. Some products shown in this catalogue are equipped with optional accessories. Please see your local dealer.